

Full Height Backsplash Reminders

1. Process

- Please be aware that adding full height backsplash may extend the overall timeline of the project **up to approximately 2-4 weeks**, as we will visit your home 4 times:

Countertop Template —————→ Countertop Installation

Template for Backsplash —————→ Backsplash Installation

2. Faucet and Cooktop Installation:

- After the countertops are installed, refrain from connecting the faucet and cooktop until the full-height backsplash is in place. **It will not be possible to install the backsplash if faucet and cooktop are installed.**

3. Gas Stove:

- If you have a gas stove, please ensure that it is disconnected, so it can be easily moved out to facilitate the template and installation of the full-height backsplash.

4. Outlet & Switches:

- Outlet and switch covers must be removed prior to the installation of the full-height backsplash. It is the homeowner's/contractor's responsibility to reattach them upon job completion.
- To safeguard our installation team, **it's essential to deactivate the power supply** to the outlets to prevent any risk of electrical accidents.
- To achieve the best aesthetic results, it's recommended that all upper cabinets, outlets, and switches are of the same height and level.
- To successfully and correctly install the full-height backsplash, switches and outlets must be positioned at least 2-3 inches away from the edge of the backsplash.

5. Gaps:

- Gaps between the backsplash and the cabinet are intentionally made for the installation process. The backsplash must be slightly smaller to fit between the countertop and cabinet, stove, or window sill. Granite Depot is not responsible for any gaps caused by uneven wall surfaces.

6. Walls:

- Prior to the template for the Full Height Backsplash, the walls must be prepared thoroughly for accurate measurements and smooth installation. This preparation includes the removal of any existing tiles, as well as clearing off old glue, silicone, or any other residues to ensure a clean surface.

Customer's signature: _____ **Date:** _____