

TEMPLATE REMINDERS

1. Cabinets

- All cabinets must be **installed, level and well supported** prior to the template appointment
- If there is a lazy susan cabinet - wall support frame behind it must be installed prior
- In case customer's cabinets require installation, repair, leveling, or rearrangement, the template for the countertop cannot be completed until all necessary work on the cabinets has been finished.



2. Working space

- Counters must be clear of all personal items.
- During the template process, the work area must be clear of other workers (not associated with Granite Depot) and customers. This is necessary to allow for the laser templator to be used effectively and accurately calibrated. Once the template is finished, customers will be welcome to enter the work area to review and discuss any questions they may have.



3. Customer Provided Sink

If customers provide their own sink, it is their responsibility to ensure the following:


- For new sinks: The customer must provide the sink to the template technician or bring it to the shop before the fabrication process begins.
- For reused sinks: The customer must disconnect the sink from the old countertop, clean it of any silicone residue, and provide it to the template technician or bring it to the shop before the fabrication process begins.

4. Farm/ Apron Front Sink

- If customers have a Farm/Apron Front sink - it must be installed, level and set 1/8"-1/16" below cabinet **prior to template**

5. Stove and Cooktop

- If customers are purchasing a new **cooktop** for their kitchen, it must be at their home by the day of the template appointment. This is necessary for the template technician to accurately check the cutout size to fit into the countertops.
- If there is a **gas stove**, please ensure that it is disconnected, so it can be easily moved out to facilitate the template and installation processes.



6. Appliance Garage

- Must be removed prior to template

Customer Signature: _____

Date: _____